


AD-A105 545

HOSKINS-WESTERN-SONDEREGGER INC LINCOLN NE
NATIONAL DAM SAFETY PROGRAM, ALLGEYER LAKE DAM (MO 30376), MISS--ETC(U)
JUN 79 R S DECKER, G JAMISON, O ULMER DACW43-79-C-0046

NL

UNCLASSIFIED

1 of 1
AD-A105 545



END
DATE
FILMED
11-81
DTIC

MISSISSIPPI - KASKASKIA - ST. LOUIS BASIN

AD A105545

ALLGEYER LAKE DAM

MONTGOMERY COUNTY, MISSOURI

MO. 30376

**PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



**United States Army
Corps of Engineers**
... Serving the Army
... Serving the Nation

St. Louis District

001 15 1981

A

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

This document has been approved
for public release and sale; its
distribution is unlimited.

JUNE, 1979

81 10 15

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A105545	
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Allgeyer Lake Dam (MO 30376) Montgomery County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Hoskins-Western-Sonderegger, Inc. Rey S. /Decker Gordon /Jamison Garold /Ulmer Harold P. /Hoskins		6. PERFORMING ORG. REPORT NUMBER
9. PER U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSD-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-79-C-0046
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSD-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 5.1.1
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program. Allgeyer Lake Dam (MO 30376), Mississippi - Kaskaskia - St. Louis Basin, Montgomery County, Missouri. Phase I Inspection Report.		12. REPORT DATE June 1979
16. DISTRIBUTION STATEMENT Approved for release; distribution unlimited.		13. NUMBER OF PAGES Approximately 54
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		

DD FORM 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

ALLGEYER LAKE DAM
MONTGOMERY COUNTY, MISSOURI
MISSOURI IDENTIFICATION NO. 30376

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY
HOSKINS-WESTERN-SONDEREGGER, INC.
CONSULTING ENGINEERS
LINCOLN, NEBRASKA

UNDER DIRECTION OF
ST. LOUIS DISTRICT, CORPS OF ENGINEERS

FOR
GOVERNOR OF MISSOURI
JUNE, 1979

Approved	
Reviewed	
Checked	
Drawn	
Plotted	
Filed	
Indexed	
Released	
Retained	
Destroyed	

A



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 NORTH 12TH STREET
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Allgeyer Lake Dam Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Allgeyer Lake Dam.

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, non-emergency by the St. Louis District as a result of the application of the following criteria:

- 1) Spillway will not pass 50 percent of the Probable Maximum Flood.
- 2) Overtopping could result in dam failure.
- 3) Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY SIGNED 19 MAR 1980
Chief, Engineering Division Date

APPROVED: SIGNED 19 MAR 1980
Colonel, CE, District Engineer Date

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

TABLE OF CONTENTS

<u>PARAGRAPH NO.</u>	<u>TITLE</u>	<u>PAGE NO.</u>
	Assessment Summary	
	Overview Photograph	
SECTION 1 - PROJECT INFORMATION		
1.1	General	1
1.2	Description of Project	1
1.3	Pertinent Data	2
SECTION 2 - ENGINEERING DATA		
2.1	Design	6
2.2	Construction	6
2.3	Operation	6
2.4	Evaluation	6
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	7
3.2	Evaluation	9
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	10
4.2	Maintenance of Dam	10
4.3	Maintenance of Operating Facilities	10
4.4	Description of Any Warning System in Effect	10
4.5	Evaluation	10
SECTION 5 - HYDRAULIC/HYDROLOGIC		
5.1	Evaluation of Features	11
SECTION 6 - STRUCTURAL STABILITY		
6.1	Evaluation of Structural Stability	13
SECTION 7 - ASSESSMENT/REMEDIAL MEASURES		
7.1	Dam Assessment	14
7.2	Remedial Measures	14

APPENDIX A - MAPS

Plate A-1	Vicinity Topography
Plate A-2	Location Map

APPENDIX B - PHOTOGRAPHS

Plate B-1	Photo Index
Plate B-2	Photo No. 2 Upstream Slope Taken from Right Side
	Photo No. 3 Crest Taken from Right Side
Plate B-3	Photo No. 4 Principal Spillway Riser
	Photo No. 5 Downstream from Sta. 3 + 50
Plate B-4	Photo No. 6 View Upstream in Emergency Spillway
	Photo No. 7 View downstream in Emergency Spillway Showing Road Spanning Spillway
Plate B-5	Photo No. 8 Crest Looking Across Emergency Spillway
	Photo No. 9 View Downstream in Emergency Spillway
Plate B-6	Photo No. 10 Downstream End of Principal Spillway
	Photo No. 11 Downstream Channel From Principal Spillway
Plate B-7	Photo No. 12 Downstream Slope Taken from Right End
	Photo No. 13 Overview Taken from Upstream On Right Side

APPENDIX C - PROJECT PLATES

Plate C-1	Soil Conservation Service - Dam Section
Plates C-2 to C-5	Soil Conservation Service - Slope Staking Notes
Plate C-6	Phase I - Plan and Centerline Profile of Dam
Plate C-7	Phase I - Section of Dam, Profile and Section of Emergency Spillway

APPENDIX D - HYDRAULIC AND HYDROLOGIC DATA

Plates D-1 & D-2	Hydrologic Computations
Plate D-3	Principal Spillway Rating Curve
Plate D-4	Emergency Spillway Rating Curve
Plate D-5	Inflow-Outflow Curves
Plates D-6 to D-19	Computer Input and Output for Ratios of PMF

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
ASSESSMENT SUMMARY

Name of Dam	Allgeyer Lake Dam
State Located	Missouri
County Located	Montgomery County
Stream	Tributary Dry Fork
Date of Inspection	June 26, 1979

Allgeyer Lake Dam was inspected by an interdisciplinary team of engineers from Hoskins-Western-Sonderregger, Inc. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.


The guidelines used in the assessment were furnished by the Department of the Army, Office of the Chief of Engineers, and developed with the help of several Federal and State agencies, professional engineering organizations, and private engineers. Based on these guidelines, this dam is classified as a small size dam with a high downstream hazard potential. Failure would threaten life and property. The estimated damage zone extends approximately two miles downstream of the dam. Within the damage zone are 3 to 4 dwellings in the Village of Americus and two crossings of Highway "p".

Our inspection and evaluation indicates that the spillways do not meet the criteria set forth in the recommended guidelines for a small dam having a high hazard potential. Considering the small volume of water impounded and the large floodplain downstream one-half of the Probable Maximum Flood is the appropriate spillway design flood. The spillways will not pass the 100-year flood (flood having a one percent chance of being exceeded in any year) without overtopping the dam. The spillways will pass 7% of the Probable Maximum Flood without overtopping the dam. The Probable Maximum Flood (PMF) is defined as the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region.

No design data were available for this dam. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These analyses should be obtained in the future.

Other deficiencies observed during the inspection are: small trees growing on the upstream and downstream slopes; potholes and ponding water on the dam crest; the lack of a trash rack on the riser of the principal spillway; the construction of a culvert and roadway across the emergency spillway; and the badly overgrown condition of trees and brush around the principal spillway outlet and the downstream channel.


Items of preventative maintenance need to be initiated by the owner as described in more detail in the body of the report.




Rey S. Decker
E-3703



Gordon Jamison



Garold Ulmer
E-4777



Harold P. Hoskins
Chairman of Board
Hoskins-Western-Sonderegger, Inc.
E-8696



PHOTO NO. 1 - OVERVIEW

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
ALLGEYER LAKE DAM - MO 30376
MONTGOMERY COUNTY, MISSOURI

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

- a. Authority. The National Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, District Engineer directed that a safety inspection of Allgeyer Lake Dam be made.
- b. Purpose of Inspection. The purpose of the inspection was to make an assessment of the general condition of the dam with respect to safety, based upon available data and visual inspection, in order to determine if the dam poses hazards to human life or property.
- c. Evaluation Criteria. Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief of Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report of the Chief of Engineers on the National Program of Inspection of Dams", dated May, 1975, and published by the Department of the Army, Office of the Chief of Engineers.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam and Appurtenances.
 - (1) The dam is an earth fill approximately 530 feet in length and about 28.7 feet in height. Topography of the area is moderately rolling with moderately steep, narrow valleys.
 - (2) The principal spillway consists of a 12" corrugated metal pipe riser with 12" diameter corrugated metal pipe conduit passing through the embankment. Two anti-seep collars are shown on the plans.
 - (3) A vegetated earth emergency spillway is cut through the left abutment.

(4) Pertinent physical data are given in paragraph 1.3 below.

- b. Location. The dam is located in the southwest corner of Montgomery County, Missouri, as shown on Plate A-2. The dam is shown on Plate A-1 in the NW $\frac{1}{4}$ of Section 14, T46N, R6W. The lake formed behind the dam is shown in the NW $\frac{1}{4}$ of Section 14, T46N, R6W.
- c. Size Classification. Criteria for determining the size classification of dams and impoundments are presented in the guidelines referenced in paragraph 1.1c above. Based on these criteria, this dam and impoundment is in the small size category.
- d. Hazard Classification. Guidelines for determining hazard classification are presented in the same guidelines as referenced in paragraph 1.1c above. Based on these guidelines, this dam is in the High Hazard Classification. The estimated damage zone extends approximately two miles downstream of the dam. Within the damage zone are 3 or 4 dwellings in the Village of Americus and two crossings of Highway "P".
- e. Ownership. The dam is owned by Edward E. Allgeyer, R.R. No. 3, Hermann, MO 65041.
- f. Purpose of Dam. The dam impounds a recreational lake covering about 5 acres.
- g. Design and Construction History. Very limited design information was supplied by the Soil Conservation Service, Columbia, MO. The first plans for the dam, dated 1963, show top of dam at elevation 100.8 and principal spillway at elevation 96. Prior to construction, Mr. Allgeyer requested that the plans be revised to provide a larger reservoir. The revised plans, dated 1965, are shown in Appendix C. The original plans, not included, are essentially the same as shown in Appendix C except for a lower dam. According to this information the dam was constructed in 1966. Mr. Allgeyer stated that a foundation cutoff trench was excavated to depths of 25 feet or more to intercept gravel strata toward the left abutment, and material for the dam was borrowed largely from the left abutment and slopes adjacent to the reservoir area. These soils were observed to be CL-CH materials.

- h. Normal Operating Procedure. There are no operating facilities for this dam.

1.3 PERTINENT DATA

- a. Drainage Area. 96.9 acres (0.15 square miles).

- b. Discharge at Damsite.

- (1) All discharges at the damsite are through an uncontrolled 12" CMP riser and conduit principal spillway, and an 18" uncontrolled CMP culvert emergency spillway placed in an embankment blocking the old earthen channel spillway.
- (2) Estimated maximum flood at damsite -- shortly after construction was completed, a 15" rain caused water to rise within approximately one foot of top of dam (culvert not in place in spillway at time of flood).
- (3) The principal spillway capacity varies from 0 cfs at elevation 756.6 feet to 0.4 cfs at the crest of the emergency spillway (elevation 757.0 feet) and to 6.2 cfs at the minimum top of dam (elevation 759.7 feet).
- (4) The emergency spillway capacity varies from 0 cfs at its crest elevation 757.0 feet to 10 cfs at elevation 759.7 feet (minimum top of dam).
- (5) Total spillway capacity at the minimum top of dam is 16 cfs \pm .

- c. Elevations (feet above M.S.L.).

- (1) Top of dam - 759.7 (low point)
- (2) Principal spillway crest - 756.6 (spillway riser notch)
- (3) Emergency spillway crest 757.0 (culvert invert)
- (4) Streambed at centerline - 731 \pm
- (5) Maximum tailwater - unknown

- d. Reservoir. Length (feet) of maximum pool - 1,000 \pm .

- e. Storage (Acre-feet).

- (1) Principal spillway to top of dam - 15 \pm
- (2) Emergency spillway - 43 \pm
- (3) Principal spillway - 43 \pm

f. Reservoir Surface (Acres).

- (1) Top of dam - 7.5 ±
- (2) Principal spillway crest - 5 ±

g. Dam.

- (1) Type - earth fill
- (2) Length - 530 feet ±
- (3) Height - 28.7 feet ±
- (4) Top width - 11 feet
- (5) Side Slopes.
 - (a) Downstream - plans show 2H on 1V; measured = 1.8/2.4 H on 1V
 - (b) Upstream - plans show 3H on 1V; measured 2.5H on 1V exposed.
- (6) Zoning - unknown
- (7) Impervious core - unknown
- (8) Cutoff - reported by Mr. Allgeyer to be constructed with 10 foot bottom width, 1H on 1V side slopes and depth of 4 to 25 feet.
- (9) Grout curtain - unknown
- (10) Wave protection - none
- (11) Internal drainage - unknown

h. Diversion Channel and Regulating Tunnel. None

i. Spillway.

- (1) Principal
 - (a) Type - uncontrolled, corrugated metal pipe, 12 inch diameter riser with 12 inch diameter conduit passing through the embankment.
 - (b) Crest (invert) elevation of notch - 756.6 feet ±
Outlet - 730.7 feet ±
 - (c) Length - 108 feet ±
- (2) Emergency
 - (a) Type - uncontrolled, vegetated earth cut through left abutment.
 - (b) Control section - consists of an 18 inch CMP culvert placed through the roadway crossing the spillway.
 - (c) Crest elevation - 757 feet
 - (d) Upstream Channel - vegetated earth
 - (e) Downstream Channel - vegetated earth on 3% slope

- j. Regulating Outlets. The only regulating outlet is an insignificant drawdown facility consisting of a 4 inch steel pipe reduced to a 1 inch pipe with valve at the outlet end.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

Limited data were available for this dam from the Soil Conservation Service, Columbia, MO. These are included with this report in Appendix C. The dam was originally designed with a maximum height of 20 feet. At the time of construction, it was decided by the owner to increase the height of the dam.

2.2 CONSTRUCTION

The only construction data available were some construction stake out notes, shown in Appendix C. These notes show the unsettled top of dam at assumed elevation of 107.5 feet \pm which would be estimated M.S.L. elevation 760.8 feet.

2.3 OPERATION

No data were available on spillway operation. It was reported by Mr. Allgeyer that shortly after the dam was built, a 15 inch rain in the area produced a flow of 2 feet or more in the emergency spillway (reservoir was within one foot \pm of the top of dam). However, this flow condition was prior to placement of the road culvert in the spillway.

2.4 EVALUATION

- a. Availability. The available data were secured from the State Office of the Soil Conservation Service, Columbia, MO.
- b. Adequacy. The available data, the field surveys and visual observations presented herein are considered adequate to support the conclusions of this report. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.
- c. Validity. The data are applicable to this dam.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

- a. General. A visual inspection of the Allgeyer Dam was made on June 26, 1979. Engineers from Hoskins-Western-Sonderegger, Inc., Lincoln, Nebraska making the inspection were: R.S. Decker, Geotechnical; Gordon Jamison, Hydrology; Garold Ulmer, Civil Engineer. Mr. Edward Allgeyer accompanied the team on the inspection.
- b. Dam.
 - (1) Geology and Soils (Abutment and embankment). The dam is located in the central Mississippi Valley wooded slope physiographic area. Upland soils consist of thin loessial material over glacial till or limestone. Valley slope materials consist of colluvium from upland loess and/or soils developed from glacial till, limestone, shale or sandstone. Fine grained sandstone is exposed in the right abutment, probably the St. Peter formation of middle Ordovician age. Mr. Allgeyer reported that the sandstone extends into the reservoir area some 100 to 150 feet from the right end of the dam and is at least 40 feet in thickness. No other bedrock formations were exposed in the area of the dam. Materials in the left abutment consist of light yellow brown CL-CH material probably derived from what appeared to be fine grained glacial till. Foundation materials apparently consist of fine grained, unjointed sandstone under the right one-third of the dam, alluvial materials containing gravel strata under the central section and fine grained glacial till under the left end of the dam.
 - (2) Upstream Slope. The slope is fairly well vegetated with adapted grasses. A few small willows are growing just up from the waterline. No significant erosion was noted. No rodent holes, cracks, or abnormal deformations were observed.
 - (3) Crest. The crest is covered with cherty gravel and serves as a roadway. A few potholes and ponding water were observed on the crest. Measurements along

the centerline indicate that the center section is about 1.5 feet higher than the ends, probably due to overfill to compensate for settlement which hasn't occurred. No cracks or deformations were observed. The maximum crest elevation of 761.5 feet (measured) is slightly higher than the revised plan elevation of 107.5 (unsettled top) which is equivalent to elevation 760.8 feet.

- (4) Downstream Slope. The downstream slope is well vegetated with adapted grasses and sweet clover. A few small cedar and cottonwood trees are growing on the slope. No evidence of seepage on the slope or along the toe was observed. It was reported by Mr. Allgeyer that there was some seep in the right abutment trough when the reservoir first filled (through the sandstone abutment) but it soon stopped. There was no evidence of this seep of the time of inspection. No rodent holes, cracks, or abnormal deformations were noted on the slope or at the toe. The berm near the toe of the slope was added soon after the dam was completed. A small sewage lagoon is located about 150 feet downstream from the right end of the dam. It should not affect the stability nor operation of the dam.

Soils on the downstream slope are plastic CL-CH materials. Measurements indicate that the upper part of the dam is slightly steeper and the lower part flatter than the 2H on 1V planned.

- (5) Miscellaneous. The vegetative cover and the nature of materials in the dam would indicate that this structure could withstand considerable overtopping without serious damage.

c. Appurtenant Structures.

- (1) The principal spillway consists of a short 12 inch diameter CMP riser attached to a 12 inch CMP conduit. Original plans called for a straight pipe with hooded inlet. No trash guard was present on the inlet riser. The outlet end was about half submerged at the time of inspection. The outlet end of the conduit was apparently extended 12 to 14 feet when the berm

was constructed along the toe of the dam. The riser pipe appears to be quite rusty. No deterioration of the pipe was noted at the lower end. The reservoir level was about 8 inches below the crest of the riser when inspected.

(2) The emergency spillway consists of a vegetated earth channel controlled by an 18 inch diameter CMP culvert through the roadway that crosses the spillway. The roadway and culvert were installed in the spillway a couple of years after the dam was constructed. No erosion was noted in the spillway or exit section. The trash line upstream from the culvert indicated that the reservoir level had been up to or slightly above the invert elevation of the pipe. Discharge from the spillway should not impair the integrity of the dam.

(3) Drawdown Facilities. A 4 inch steel pipe reduced to a 1 inch diameter pipe and valve at the outlet end passes through the base of the dam. The valve is operable and Mr. Allgeyer reported that the line would drawdown the reservoir level about 1 inch per day.

d. Reservoir Area. No slides were observed nor significant erosion noted around the shoreline of the reservoir. Upstream from the right end of the dam a natural sand beach has been developed for swimming.

e. Downstream Channel. The channel downstream from the principal spillway and the scour hole are badly overgrown with trees and brush. The spillway appears to be stable.

3.2 EVALUATION

This dam appears to be in good shape structurally with no serious potential of failure. Measurements taken during the inspection indicate that it was generally constructed according to the revised plans, except that the principal and emergency spillways were modified and will not operate as planned. The material in the dam and the embankment slopes, with the added downstream berm, should provide adequate safety against shear failure for a dam of this height. The trees should be removed from the embankment slopes.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The pool level is controlled by rainfall, infiltration, evaporation, and the capacity of the uncontrolled spillways. A very small valve operated drawdown facility will lower the lake level about 1 inch per day (according to the owner).

4.2 MAINTENANCE OF DAM

Maintenance of the dam appears to be fairly good except for tree growth on the slopes, particularly the downstream slope.

4.3 MAINTENANCE OF OPERATING FACILITIES

No operating facilities exist at this dam.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no warning system in effect for this dam.

4.5 EVALUATION

There does not appear to be any serious potential of failure of this structure.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

- a. Design Data. Sketchy plans for this dam were obtained from the Soil Conservation Service, Columbia, Missouri. Spillway conditions found in the field differ considerably from the plans.
- b. Experience Data. The drainage area, reservoir surface area, and elevation-storage data were developed from the USGS Americus, Missouri 7 1/2 minute topographic quadrangle map. The hydraulic computations for the spillway and dam overtopping discharge ratings were based on data collected in the field at the time of the field inspection.
- c. Visual Observations.
 - (1) The fill and culvert that have been constructed in the original emergency spillway channel must have a significant effect on the outflow capacity for the reservoir.
 - (2) Apparently the originally planned hooded inlet for the principal spillway has been replaced with a short riser section.
- d. Overtopping Potential. The spillways are too small to pass either the 100-year or one-half probable maximum flood without overtopping. The spillways will pass .07 PMF without overtopping. The spillways will pass the 10-year flood without overtopping. The dam could withstand considerable overtopping without serious damage. The results of the routings through the dam are tabulated in regards to the following conditions.

<u>Frequency</u>	<u>Inflow Discharge cfs</u>	<u>Outflow Discharge cfs</u>	<u>Maximum Pool Elevation</u>	<u>Freeboard Top of Dam Min. Elev. 759.7</u>	<u>Time Dam Overtopping Hr.</u>
10 Yr.	200	13	759.0	+0.7	-
100 Yr.	360	45	760.3	-0.6	8-
0.5 PMF	870	810	761.2	-1.5	12-
PMF	1740	1730	761.7	-2.0	14+
*0.07 PMF	130	16	759.7	0	-

*Percent PMF passed by spillways.

According to the recommended guidelines from the Department of the Army, Office of the Chief of Engineers, this dam is classified as having a high hazard rating and a small size. Therefore, the 1/2 PMF to PMF is the test for the adequacy of the dam and its spillways.

The estimated damage zone is described in Paragraph 1.2d in this report.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observation. This dam appears to be structurally stable. There is no indication of seepage, and the slopes and embankment materials should be safe against shear failure. The effects of overtopping on structural stability are not known, but it would appear that the dam would not be seriously damaged by such an occurrence. Tree growth on the slopes could lead to potential of failure if left uncontrolled.
- b. Design and Construction Data. There was not sufficient design or construction data available to assess the structural stability of the dam. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Operating Records. There are no controlled operating facilities for this dam.
- d. Post Construction Changes. The berm at the downstream toe was added after the initial construction of the dam. The emergency spillway was also altered by construction of a roadway with culvert across the control section. The construction plan shows a hooded inlet at the upstream end of the principal spillway instead of the corrugated metal pipe riser with which the spillway is now equipped.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of the magnitude predicted in this area is not expected to cause structural failure of a dam of this height which is constructed of CL-CH materials.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Safety. This structure looks good and does not appear to have a serious potential of failure. The apparent material in the embankment and the slope parameters should provide adequate structural stability. Analyses presented in Section 5 indicate that the dam will be overtopped 1.5 feet for a period of 12 hours + by one-half the Probable Maximum Flood. Additional studies would be required to determine the effects of such overtopping on the structural and erosional stability of the dam. Uncontrolled tree growth on the dam could ultimately lead to potential of failure. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- b. Adequacy of Information. The conclusions in this report are based upon limited design data, performance history and visual observations. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.
- c. Urgency. The items recommended in paragraph 7.2a should be pursued on a high priority basis.
- d. Necessity for Phase II. Phase II investigation is not considered necessary.
- e. Seismic Stability. This dam is located in Seismic Zone 1. An earthquake of this magnitude is not expected to be hazardous to this dam.

7.2 REMEDIAL MEASURES


- a. Alternatives.
 - (1) Additional information should be obtained to determine the effects of the road grade and culvert obstruction in the emergency spillway and to determine the increase in the height of dam or the size of the spillway that is required to pass one-half the Probable Maximum


Flood without overtopping the dam. The services of an engineer experienced in the design and construction of dams should be obtained to evaluate the potential of overtopping and its effects on structural and erosional stability, to provide seepage and stability analyses of the present dam and to design protective measures, if required.

b. O & M Procedures


- (1) The trees and brush growing on the embankment slopes and in the principal spillway outlet channel should be removed and measures taken to prevent recurrent growth.
- (2) The principal spillway should have some sort of trash rack to insure efficient operation.
- (3) Potholes on the crest should be filled and surface drainage provided for the crest.
- (4) A program of regular inspection and maintenance should be initiated to control tree growth on the dam and to evaluate the condition of the principal spillway riser and conduit.

APPENDIX A
MAPS





APPENDIX B
PHOTOGRAPHS



Scale: 1"=200'

PHOTO INDEX

ALLGEYER LAKE DAM

MONTGOMERY COUNTY, MISSOURI

MO. 30376

PLATE B-1



PHOTO NO. 2 - UPSTREAM SLOPE TAKEN FROM RIGHT SIDE.



PHOTO NO. 3 - CREST TAKEN FROM RIGHT SIDE



PHOTO NO. 4 - PRINCIPAL SPILLWAY RISER



PHOTO NO. 5 - DOWNSTREAM FROM STA. 3+50



PHOTO NO. 6 - VIEW UPSTREAM IN EMERGENCY SPILLWAY



PHOTO NO. 7 - VIEW DOWNSTREAM IN EMERGENCY SPILLWAY SHOWING
ROAD SPANNING SPILLWAY



PHOTO NO. 8 - CREST LOOKING ACROSS EMERGENCY SPILLWAY



PHOTO NO. 9 - VIEW DOWNSTREAM IN EMERGENCY SPILLWAY



PHOTO NO. 10 - DOWNSTREAM END OF PRINCIPAL SPILLWAY




PHOTO NO. 11 - DOWNSTREAM CHANNEL FROM PRINCIPAL SPILLWAY



PHOTO NO. 12 - DOWNSTREAM SLOPE TAKEN FROM RIGHT END




PHOTO NO. 13 - OVERVIEW TAKEN FROM UPSTREAM ON RIGHT SIDE



APPENDIX C
PLAN, PROFILES & SECTION


SCD <i>Montgomery</i>	Date <i>1-11-66</i>
Work Unit	
Farmer-Group <i>Pittenger Bros</i>	
Location	
Job <i>Slope stakes</i>	
Design Sur.	Const. Layout <input checked="" type="checkbox"/>
Const. Check	Other <input type="checkbox"/>
Dist. Agri. No.	Field No.
ACP No.	

PLATE C-2


Sta.	B.S.	H.I.	F.S. or Grade Rod	Elev. or Planned Elev.
2450		1069		
			24.2	23.6
				107.5
3450			19.4	16.8
				107.2
4450			6.6	6.0
				106.6








DAM SECTION AT STA. 3+50
Scale: 1" = 20'



E PROFILE OF SPILLWAY
Scale: 1" = 10' H.
1" = 5 V.



SPILLWAY SECTION (E of Dam)
Scale: 1" = 10' H.
1" = 2.5 V.

APPENDIX D
HYDROLOGIC COMPUTATIONS

HYDROLOGIC COMPUTATIONS


1. The SCS dimensionless unit hydrograph and the systemized computer program HEC-1 (Dam Safety Version), July 1978, prepared by the Hydrologic Engineering Center, U.S. Corps of Engineers, Davis, California, were used to develop the inflow hydrographs.
 - a. Twenty-four hour, 100-year rainfall for the dam location was taken from the data for the rainfall station at Sullivan, MO as supplied by the St. Louis District, Corps of Engineers per their letter dated 6 March 1979. The twenty-four hour probable maximum precipitation was taken from the curves of Hydrometeorological Report No. 33 and current Corps of Engineers and St. Louis District policy and guidance for hydraulics and hydrology.
 - b. Drainage area = 0.15 square miles (96.9 acres).
 - c. Time of concentration of runoff = 11 minutes (computed from "Kirpich" formula).
 - d. The antecedent storm conditions for the probable maximum precipitation were heavy rainfall and low temperatures which occurred on the previous 5 days (SCS AMC III). The antecedent storm conditions for the 100-year precipitation were an average of the conditions which have preceded the occurrence of the maximum annual flood on numerous watersheds (SCS AMC II). The initial pool elevation was assumed at the crest of the notch in the CMP riser.
 - e. The total twenty-four hour storm duration losses for the 100-year storm were 3.42 inches. The total losses for the PMF storm were 2.03 inches. These data are based on SCS runoff curve No. 85 and No. 70 for antecedent moisture conditions SCS AMC III and AMC II, respectively. The watershed is composed of primarily SCS soil group C (Hatton-Keswick-Goss-Gasconade soils) and consists mostly of woodland with some alfalfa and grass.
 - f. Average soil loss rates = 0.10 inch per hour approximately.
2. The discharge ratings for the principal spillway were developed using equations for orifice, weir, and full conduit flow. They are as follows:


- a. Orifice flow equation ($Q = CA\sqrt{2gH}$)
 where C = orifice coefficient = 0.6
 A = area of opening, ft.² = 0.785
 H = total head, ft.
- b. Weir flow equation ($Q_w = CLH^{3/2}$)
 where C = weir coefficient = 3.5
 L = length of weir, ft. = 3.14
 H = total head, ft.
- c. Full conduit flow equation ($Q = a\sqrt{\frac{2gH}{1 + K_e + K_b + K_p L}}$)
 where a = cross-sectional area of pipe, ft.² = 0.785
 H = total head, ft.
 K_e = coefficient for entrance loss = 0.5
 K_b = coefficient for bend loss = 0.75
 K_p = coefficient for pipe friction loss = 0.1157
 L = length of pipe, ft. = 107

The emergency spillway rating was developed using nomograph for C.M. Pipe culverts with inlet control from the BPR Manual on Highway Culverts, Jan. 1963.

The flows over the dam crest were developed using HEC-1 (Dam Safety Version) program with a discharge coefficient of 2.9 and a value of 1.5 for the exponent of head.

3. Floods were routed through the reservoir using the HEC-1 (Dam Safety Version) program to determine the capabilities of the spillway and dam embankment crest. The output and plotted hydrographs are shown in this Appendix.





DIETZEN CORPORATION
MADE IN U.S.A.

NO. 340R-10 DIETZEN GRAPH PAPER
10 X 10 PER INCH




PLATE D-5

DATE RECEIVED: NOV. 07

 RECD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VISSION JULY 1978
 LAST MODIFICATION 26 FEB 75

RUN DATE 7/26/75
 TIME 11:40:25

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF
 HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF ALLGEYER LAKE DAM 30376
 RATIOS OF PMF ROUTED THROUGH THE RESERVOIR

JOB SPECIFICATION											
NO	HR	NPIN	IOAY	INR	IMIN	MTBC	IPLT	IPRT	ISTAN		
288	0	5	C	0	0	0	0	3	0		
JOB SPECIFICATION											
NO	HR	NPIN	IOAY	INR	IMIN	MTBC	IPLT	IPRT	ISTAN		
288	0	5	C	0	0	0	0	3	0		

MULTI-PLAN ANALYSES TO BE PERFORMED

PPLAN= 1 NRTIN= 9 LRTIN= 1

RATIOS= .05 .10 .15 .20 .35 .50 .65 .80 1.00

SUB-AREA RUNOFF COMPUTATION

CALCULATION OF INFLO HYDRO TO RES 30376

ISIAQ	ICOMP	TECON	ITAPE	JPT	JPT	INAME	ISTAGE	TAUTO
000001	0	0	C	0	0	1	0	0

HYDROGRAPH DATA

HYDRO	ISIAQ	ICOMP	TECON	ITAPE	JPT	JPT	INAME	ISTAGE	TAUTO
1	2	.15	0.00	.15	1.00	0.000	0	1	0

PRECIP DATA

SPEE	PMS	R6	R12	R24	R48	R72	R96
0.00	25.00	162.00	121.00	130.00	0.00	0.00	0.00

LOSS DATA

LRCT	STKR	DLTKR	RTIOL	ERAIN	STKRS	PTIUK	STRTL	CASIL	ALSHK	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-85.00	0.00	0.00

CURVE NO = -85.00 WETNESS = -1.00 EFFECT CN = 85.00

UNIT HYDROGRAPH DATA

IC= 0.00 LAG= .17

RECESSION DATA

SIRTO= 0.00 ORCSN= .01 RIHUR= 1.00

UNIT HYDROGRAPH 12 END OF PERIOD ORDINATES, IC= 0.00 HOURS, LAG= .17 VOL= 1.00
 105. 417. 126. 204. 102. 55. 25. 15. 0. 4.

END-OF-PERIOD FLOW

1.01	10.15	123	.07	.06	.01	69.	1.01	22.15	267	.02	.02	.00	22.
1.01	10.20	124	.07	.06	.01	69.	1.01	22.20	268	.02	.02	.00	22.
1.01	10.25	125	.07	.06	.01	70.	1.01	22.25	269	.02	.02	.00	22.
1.01	10.30	126	.07	.06	.01	70.	1.01	22.30	270	.02	.02	.00	22.
1.01	10.35	127	.07	.06	.01	70.	1.01	22.35	271	.02	.02	.00	22.
1.01	10.40	128	.07	.06	.01	70.	1.01	22.40	272	.02	.02	.00	22.
1.01	10.45	129	.07	.06	.01	70.	1.01	22.45	273	.02	.02	.00	22.
1.01	10.50	130	.07	.06	.01	70.	1.01	22.50	274	.02	.02	.00	22.
1.01	10.55	131	.07	.06	.01	70.	1.01	22.55	275	.02	.02	.00	22.
1.01	11.00	132	.07	.06	.01	71.	1.01	23.00	276	.02	.02	.00	22.
1.01	11.05	133	.07	.06	.01	71.	1.01	23.05	277	.02	.02	.00	22.
1.01	11.10	134	.07	.06	.01	71.	1.01	23.10	278	.02	.02	.00	22.
1.01	11.15	135	.07	.06	.00	71.	1.01	23.15	279	.02	.02	.00	22.
1.01	11.20	136	.07	.06	.00	71.	1.01	23.20	280	.02	.02	.00	22.
1.01	11.25	137	.07	.06	.00	71.	1.01	23.25	281	.02	.02	.00	22.
1.01	11.30	138	.07	.06	.00	71.	1.01	23.30	282	.02	.02	.00	22.
1.01	11.35	139	.07	.06	.00	71.	1.01	23.35	283	.02	.02	.00	22.
1.01	11.40	140	.07	.06	.00	72.	1.01	23.40	284	.02	.02	.00	22.
1.01	11.45	141	.07	.06	.00	72.	1.01	23.45	285	.02	.02	.00	22.
1.01	11.50	142	.07	.06	.00	72.	1.01	23.50	286	.02	.02	.00	22.
1.01	11.55	143	.07	.06	.00	72.	1.01	23.55	287	.02	.02	.00	22.
1.01	12.00	144	.07	.06	.00	72.	1.02	0.00	288	.02	.02	.00	22.

SUM 32.50 30.47 2.03 35576.
[825.11 776.11 51.11 1007.401

CFS	1740.	405.	123.	123.	35555.
CMS	49.	11.	3.	3.	1001.
INCHES		24.92	30.42	30.42	30.42
MM		633.05	772.72	772.72	772.72
AC-IT		261.	245.	245.	245.
THOUS CU M		247.	302.	302.	302.

HYDROGRAPH AT STA000001 FOR PLAN 1, RETIO 1

CFS	87.	20.	6.	6.	1778.
CMS	2.	1.	0.	0.	50.
INCHES		1.25	1.52	1.52	1.52
MM		31.65	38.64	38.64	38.64
AC-IT		10.	12.	12.	12.
THOUS CU M		12.	15.	15.	15.

HYDROGRAPH AT STA000001 FOR PLAN 1, RETIO 2

CFS	174.	40.	12.	12.	3550.
CMS	5.	1.	0.	0.	101.
INCHES		2.49	3.04	3.04	3.04
MM		63.31	77.27	77.27	77.27
AC-IT		20.	24.	24.	24.
THOUS CU M		24.	30.	30.	30.

HYDROGRAPH AT STA000001 FOR PLAN 1, RETIO 3

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
261.	61.	19.	19.	5333.
7.	2.	1.	1.	151.
CFS				
CM5				
INCHES				
	3.74	4.56	4.56	4.56
	94.96	115.91	115.91	115.91
AC-FT	30.	37.	37.	37.
THOUS CU M	37.	45.	45.	45.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 4

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
348.	81.	25.	25.	7111.
10.	2.	1.	1.	201.
CFS				
CM5				
INCHES				
	4.98	6.08	6.08	6.08
	126.61	154.54	154.54	154.54
AC-FT	40.	49.	49.	49.
THOUS CU M	49.	60.	60.	60.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 5

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
609.	142.	43.	43.	12444.
17.	4.	1.	1.	352.
CFS				
CM5				
INCHES				
	8.72	10.65	10.65	10.65
	221.57	270.45	270.45	270.45
AC-FT	70.	86.	86.	86.
THOUS CU M	87.	106.	106.	106.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 6

0.5 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
870.	202.	62.	62.	17178.
25.	6.	2.	2.	503.
CFS				
CM5				
INCHES				
	12.46	15.21	15.21	15.21
	316.53	386.36	386.36	386.36
AC-FT	100.	122.	122.	122.
THOUS CU M	124.	151.	151.	151.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 7

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1131.	241.	80.	80.	23111.
32.	7.	2.	2.	654.
CFS				
CM5				
INCHES				
	16.20	19.77	19.77	19.77
	411.48	502.27	502.27	502.27
AC-FT	130.	159.	159.	159.
THOUS CU M	161.	196.	196.	196.

HYDROGRAPH AT STA000001 FOR PLAN 1, RTIO 8

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1392.	324.	95.	95.	28444.
CFS				

CFS 39. 9. 3. 805.
 INCHES 19.94 24.34 24.34
 MM 506.44 618.17 618.17
 AC-FT 160. 196. 196.
 THOUS CU M 158. 242. 242.

HYDROGRAPH AT STAD0001 FOR PLAN 1, RTIO 9 **PMF**

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
 CFS 1740. 405. 123. 35555.
 CFS 49. 11. 3. 1007.
 INCHES 24.92 30.42 30.42 30.42
 MM 633.05 772.72 772.72 772.72
 AC-FT 201. 245. 245.
 THOUS CU M 247. 302. 302.

ROUTED FLOODS THRU RES 3037E

HYDROGRAPH ROUTING											
STAGE	INSTAQ	ICOMP	TECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	TAUTO		
	000002	1	0	0	2	0	1	0	0		
ROUTING DATA											
QLUSS	CLOSS	AVG	IRFS	ISAME	IUPT	IPMP	ISIR				
0.0	0.000	0.00	1	1	0	0	0				
NSIPS NSTOL											
	1	0	LAG	AMSKK	X	TSK	STURA	ISPRAT			
			0	0.000	0.000	0.000	-757.	-1			
750.00	757.00	757.30	757.30	757.50	757.60	758.00	759.00	760.00	761.00		
762.00	762.80	762.90	762.90	763.00	763.00	765.00					
0.00	.40	1.60	1.60	3.10	4.40	6.90	13.30	17.30	20.70		
23.40	25.50	25.80	25.80	25.90	27.70	29.40					
0.	5.	10.	16.	22.	30.	39.	49.	59.	119.		
ELEVATION=	751.	759.	760.	761.	762.	763.	764.	765.	770.		

CRET SPWID CCOM EXPSN ELEV EL ELEV CAREA EXPI
 750.6 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0
 DAM DATA
 TOPEL COLE EXPD DAMWD
 759.7 2.9 1.5 6.30.

CREST LENGTH 70. 165. 220. 160. 470. 555. 568. 591. 630.
 AT CR PILEW 70.1 760.3 760.5 761.0 761.3 761.5 762.0 763.0 764.5
 ELEVATION=

STATION 000002, PLAN 1, RATIO 1

STORAGE

[illegible]

•(VI)•

STATION000002

	0.	100.	200.	300.	400.	500.	600.	700.	800.	900.	0.	0.
0.5	11											
1.0	21											
1.5	31											
2.0	41											
2.5	51											
3.0	61											
3.5	71											
4.0	81											
4.5	91											
5.0	101											
5.5	111											
6.0	121											
6.5	131											
7.0	141											
7.5	151											
8.0	161											
8.5	171											
9.0	181											
9.5	191											
10.0	201											
10.5	211											
11.0	221											
11.5	231											
12.0	241											
12.5	251											
13.0	261											
13.5	271											
14.0	281											
14.5	291											
15.0	301											
15.5	311											
16.0	321											
16.5	331											
17.0	341											
17.5	351											
18.0	361											
18.5	371											
19.0	381											
19.5	391											
20.0	401											
20.5	411											
21.0	421											
21.5	431											
22.0	441											
22.5	451											
23.0	461											
23.5	471											
24.0	481											
24.5	491											
25.0	501											
25.5	511											
26.0	521											
26.5	531											
27.0	541											
27.5	551											
28.0	561											
28.5	571											
29.0	581											
29.5	591											
30.0	601											
30.5	611											
31.0	621											
31.5	631											
32.0	641											
32.5	651											
33.0	661											
33.5	671											
34.0	681											
34.5	691											
35.0	701											
35.5	711											
36.0	721											
36.5	731											
37.0	741											
37.5	751											
38.0	761											
38.5	771											
39.0	781											
39.5	791											
40.0	801											
40.5	811											
41.0	821											
41.5	831											
42.0	841											
42.5	851											
43.0	861											
43.5	871											
44.0	881											
44.5	891											
45.0	901											

4.45 571
 4.50 581
 4.55 591
 5.00 601
 5.05 611
 5.10 621
 5.15 631
 5.20 641
 5.25 651
 5.30 661
 5.35 671
 5.40 681
 5.45 691
 5.50 701
 5.55 711
 6.00 721
 6.05 731
 6.10 741
 6.15 751
 6.20 761
 6.25 771
 6.30 781
 6.35 791
 6.40 801
 6.45 811
 6.50 821
 6.55 831
 7.00 841
 7.05 851
 7.10 861
 7.15 871
 7.20 881
 7.25 891
 7.30 901
 7.35 911
 7.40 921
 7.45 931
 7.50 941
 7.55 951
 7.60 961
 7.65 971
 7.70 981
 7.75 991
 7.80 1001
 7.85 1011
 7.90 1021
 7.95 1031
 8.00 1041
 8.05 1051
 8.10 1061
 8.15 1071
 8.20 1081
 8.25 1091
 8.30 1101
 8.35 1111
 8.40 1121
 8.45 1131
 8.50 1141
 8.55 1151
 8.60 1161
 8.65 1171
 8.70 1181
 8.75 1191
 8.80 1201
 8.85 1211
 8.90 1221
 8.95 1231
 9.00 1241
 9.05 1251
 9.10 1261
 9.15 1271
 9.20 1281
 9.25 1291
 9.30 1301
 9.35 1311
 9.40 1321
 9.45 1331
 9.50 1341
 9.55 1351
 9.60 1361
 9.65 1371
 9.70 1381
 9.75 1391
 9.80 1401
 9.85 1411
 9.90 1421
 9.95 1431
 10.00 1441
 10.05 1451
 10.10 1461
 10.15 1471
 10.20 1481
 10.25 1491
 10.30 1501
 10.35 1511
 10.40 1521
 10.45 1531
 10.50 1541
 10.55 1551
 10.60 1561
 10.65 1571
 10.70 1581
 10.75 1591
 10.80 1601
 10.85 1611
 10.90 1621
 10.95 1631
 11.00 1641
 11.05 1651
 11.10 1661
 11.15 1671
 11.20 1681
 11.25 1691
 11.30 1701
 11.35 1711
 11.40 1721
 11.45 1731
 11.50 1741
 11.55 1751
 11.60 1761
 11.65 1771
 11.70 1781
 11.75 1791
 11.80 1801
 11.85 1811
 11.90 1821
 11.95 1831
 12.00 1841
 12.05 1851
 12.10 1861
 12.15 1871
 12.20 1881
 12.25 1891
 12.30 1901
 12.35 1911
 12.40 1921
 12.45 1931
 12.50 1941
 12.55 1951
 12.60 1961
 12.65 1971
 12.70 1981
 12.75 1991
 12.80 2001
 12.85 2011
 12.90 2021
 12.95 2031
 13.00 2041
 13.05 2051
 13.10 2061
 13.15 2071
 13.20 2081
 13.25 2091
 13.30 2101
 13.35 2111
 13.40 2121
 13.45 2131
 13.50 2141
 13.55 2151
 13.60 2161
 13.65 2171
 13.70 2181
 13.75 2191
 13.80 2201
 13.85 2211
 13.90 2221
 13.95 2231
 14.00 2241
 14.05 2251
 14.10 2261
 14.15 2271
 14.20 2281
 14.25 2291
 14.30 2301
 14.35 2311
 14.40 2321
 14.45 2331
 14.50 2341
 14.55 2351
 14.60 2361
 14.65 2371
 14.70 2381
 14.75 2391
 14.80 2401
 14.85 2411
 14.90 2421
 14.95 2431
 15.00 2441
 15.05 2451
 15.10 2461
 15.15 2471
 15.20 2481
 15.25 2491
 15.30 2501
 15.35 2511
 15.40 2521
 15.45 2531
 15.50 2541
 15.55 2551
 15.60 2561
 15.65 2571
 15.70 2581
 15.75 2591
 15.80 2601
 15.85 2611
 15.90 2621
 15.95 2631
 16.00 2641
 16.05 2651
 16.10 2661
 16.15 2671
 16.20 2681
 16.25 2691
 16.30 2701
 16.35 2711
 16.40 2721
 16.45 2731
 16.50 2741
 16.55 2751
 16.60 2761
 16.65 2771
 16.70 2781
 16.75 2791
 16.80 2801
 16.85 2811
 16.90 2821
 16.95 2831
 17.00 2841
 17.05 2851
 17.10 2861
 17.15 2871
 17.20 2881
 17.25 2891
 17.30 2901
 17.35 2911
 17.40 2921
 17.45 2931
 17.50 2941
 17.55 2951
 17.60 2961
 17.65 2971
 17.70 2981
 17.75 2991
 17.80 3001
 17.85 3011
 17.90 3021
 17.95 3031
 18.00 3041
 18.05 3051
 18.10 3061
 18.15 3071
 18.20 3081
 18.25 3091
 18.30 3101
 18.35 3111
 18.40 3121
 18.45 3131
 18.50 3141
 18.55 3151
 18.60 3161
 18.65 3171
 18.70 3181
 18.75 3191
 18.80 3201
 18.85 3211
 18.90 3221
 18.95 3231
 19.00 3241
 19.05 3251
 19.10 3261
 19.15 3271
 19.20 3281
 19.25 3291
 19.30 3301
 19.35 3311
 19.40 3321
 19.45 3331
 19.50 3341
 19.55 3351
 19.60 3361
 19.65 3371
 19.70 3381
 19.75 3391
 19.80 3401
 19.85 3411
 19.90 3421
 19.95 3431
 20.00 3441
 20.05 3451
 20.10 3461
 20.15 3471
 20.20 3481
 20.25 3491
 20.30 3501
 20.35 3511
 20.40 3521
 20.45 3531
 20.50 3541
 20.55 3551
 20.60 3561
 20.65 3571
 20.70 3581
 20.75 3591
 20.80 3601
 20.85 3611
 20.90 3621
 20.95 3631
 21.00 3641
 21.05 3651
 21.10 3661
 21.15 3671
 21.20 3681
 21.25 3691
 21.30 3701
 21.35 3711
 21.40 3721
 21.45 3731
 21.50 3741
 21.55 3751
 21.60 3761
 21.65 3771
 21.70 3781
 21.75 3791
 21.80 3801
 21.85 3811
 21.90 3821
 21.95 3831
 22.00 3841
 22.05 3851
 22.10 3861
 22.15 3871
 22.20 3881
 22.25 3891
 22.30 3901
 22.35 3911
 22.40 3921
 22.45 3931
 22.50 3941
 22.55 3951
 22.60 3961
 22.65 3971
 22.70 3981
 22.75 3991
 22.80 4001
 22.85 4011
 22.90 4021
 22.95 4031
 23.00 4041
 23.05 4051
 23.10 4061
 23.15 4071
 23.20 4081
 23.25 4091
 23.30 4101
 23.35 4111
 23.40 4121
 23.45 4131
 23.50 4141
 23.55 4151
 23.60 4161
 23.65 4171
 23.70 4181
 23.75 4191
 23.80 4201
 23.85 4211
 23.90 4221
 23.95 4231
 24.00 4241
 24.05 4251
 24.10 4261
 24.15 4271
 24.20 4281
 24.25 4291
 24.30 4301
 24.35 4311
 24.40 4321
 24.45 4331
 24.50 4341
 24.55 4351
 24.60 4361
 24.65 4371
 24.70 4381
 24.75 4391
 24.80 4401
 24.85 4411
 24.90 4421
 24.95 4431
 25.00 4441
 25.05 4451
 25.10 4461
 25.15 4471
 25.20 4481
 25.25 4491
 25.30 4501
 25.35 4511
 25.40 4521
 25.45 4531
 25.50 4541
 25.55 4551
 25.60 4561
 25.65 4571
 25.70 4581
 25.75 4591
 25.80 4601
 25.85 4611
 25.90 4621
 25.95 4631
 26.00 4641
 26.05 4651
 26.10 4661
 26.15 4671
 26.20 4681
 26.25 4691
 26.30 4701
 26.35 4711
 26.40 4721
 26.45 4731
 26.50 4741
 26.55 4751
 26.60 4761
 26.65 4771
 26.70 4781
 26.75 4791
 26.80 4801
 26.85 4811
 26.90 4821
 26.95 4831
 27.00 4841
 27.05 4851
 27.10 4861
 27.15 4871
 27.20 4881
 27.25 4891
 27.30 4901
 27.35 4911
 27.40 4921
 27.45 4931
 27.50 4941
 27.55 4951
 27.60 4961
 27.65 4971
 27.70 4981
 27.75 4991
 27.80 5001
 27.85 5011
 27.90 5021
 27.95 5031
 28.00 5041
 28.05 5051
 28.10 5061
 28.15 5071
 28.20 5081
 28.25 5091
 28.30 5101
 28.35 5111
 28.40 5121
 28.45 5131
 28.50 5141
 28.55 5151
 28.60 5161
 28.65 5171
 28.70 5181
 28.75 5191
 28.80 5201
 28.85 5211
 28.90 5221
 28.95 5231
 29.00 5241
 29.05 5251
 29.10 5261
 29.15 5271
 29.20 5281
 29.25 5291
 29.30 5301
 29.35 5311
 29.40 5321
 29.45 5331
 29.50 5341
 29.55 5351
 29.60 5361
 29.65 5371
 29.70 5381
 29.75 5391
 29.80 5401
 29.85 5411
 29.90 5421
 29.95 5431
 30.00 5441
 30.05 5451
 30.10 5461
 30.15 5471
 30.20 5481
 30.25 5491
 30.30 5501
 30.35 5511
 30.40 5521
 30.45 5531
 30.50 5541
 30.55 5551
 30.60 5561
 30.65 5571
 30.70 5581
 30.75 5591
 30.80 5601
 30.85 5611
 30.90 5621
 30.95 5631
 31.00 5641
 31.05 5651
 31.10 5661
 31.15 5671
 31.20 5681
 31.25 5691
 31.30 5701
 31.35 5711
 31.40 5721
 31.45 5731
 31.50 5741
 31.55 5751
 31.60 5761
 31.65 5771
 31.70 5781
 31.75 5791
 31.80 5801
 31.85 5811
 31.90 5821
 31.95 5831
 32.00 5841
 32.05 5851
 32.10 5861
 32.15 5871
 32.20 5881
 32.25 5891
 32.30 5901
 32.35 5911
 32.40 5921
 32.45 5931
 32.50 5941
 32.55 5951
 32.60 5961
 32.65 5971
 32.70 5981
 32.75 5991
 32.80 6001
 32.85 6011
 32.90 6021
 32.95 6031
 33.00 6041
 33.05 6051
 33.10 6061
 33.15 6071
 33.20 6081
 33.25 6091
 33.30 6101
 33.35 6111
 33.40 6121
 33.45 6131
 33.50 6141
 33.55 6151
 33.60 6161
 33.65 6171
 33.70 6181
 33.75 6191
 33.80 6201
 33.85 6211
 33.90 6221
 33.95 6231
 34.00 6241
 34.05 6251
 34.10 6261
 34.15 6271
 34.20 6281
 34.25 6291
 34.30 6301
 34.35 6311
 34.40 6321
 34.45 6331
 34.50 6341
 34.55 6351
 34.60 6361
 34.65 6371
 34.70 6381
 34.75 6391
 34.80 6401
 34.85 6411
 34.90 6421
 34.95 6431
 35.00 6441
 35.05 6451
 35.10 6461
 35.15 6471
 35.20 6481
 35.25 6491
 35.30 6501
 35.35 6511
 35.40 6521
 35.45 6531
 35.50 6541
 35.55 6551
 35.60 6561
 35.65 6571
 35.70 6581
 35.75 6591
 35.80 6601
 35.85 6611
 35.90 6621
 35.95 6631
 36.00 6641
 36.05 6651
 36.10 6661
 36.15 6671
 36.20 6681
 36.25 6691
 36.30 6701
 36.35 6711
 36.40 6721
 36.45 6731
 36.50 6741
 36.55 6751
 36.60 6761
 36.65 6771
 36.70 6781
 36.75 6791
 36.80 6801
 36.85 6811
 36.90 6821
 36.95 6831
 37.00 6841
 37.05 6851
 37.10 6861
 37.15 6871
 37.20 6881
 37.25 6891
 37.30 6901
 37.35 6911
 37.40 6921
 37.45 6931
 37.50 6941
 37.55 6951
 37.60 6961
 37.65 6971
 37.70 6981
 37.75 6991
 37.80 7001
 37.85 7011
 37.90 7021
 37.95 7031
 38.00 7041
 38.05 7051
 38.10 7061
 38.15 7071
 38.20 7081
 38.25 7091
 38.30 7101
 38.35 7111
 38.40 7121
 38.45 7131
 38.50 7141
 38.55 7151
 38.60 7161
 38.65 7171
 38.70 7181
 38.75 7191
 38.80 7201
 38.85 7211
 38.90 7221
 38.95 7231
 39.00 7241
 39.05 7251
 39.10 7261
 39.15 7271
 39.20 7281
 39.25 7291
 39.30 7301
 39.35 7311
 39.40 7321
 39.45 7331
 39.50 7341
 39.55 7351
 39.60 7361
 39.65 7371
 39.70 7381
 39.75 7391
 39.80 7401
 39.85 7411
 39.90 7421
 39.95 7431
 40.00 7441
 40.05 7451
 40.10 7461
 40.15 7471
 40.20 7481
 40.25 7491
 40.30 7501
 40.35 7511
 40.40 7521
 40.45 7531
 40.50 7541
 40.55 7551
 40.60 7561
 40.65 7571
 40.70 7581
 40.75 7591
 40.80 7601
 40.85 7611
 40.90 7621
 40.95 7631
 41.00 7641
 41.05 7651
 41.10 7661
 41.15 7671
 41.20 7681
 41.25 7691
 41.30 7701
 41.35 7711
 41.40 7721
 41.45 7731
 41.50 7741
 41.55 7751
 41.60 7761
 41.65 7771
 41.70 7781
 41.75 7791
 41.80 7801
 41.85 7811
 41.90 7821
 41.95 7831
 42.00 7841
 42.05 7851
 42.10 7861
 42.15 7871
 42.20 7881
 42.25 7891
 42.30 7901
 42.35 7911
 42.40 7921
 42.45 7931
 42.50 7941
 42.55 7951
 42.60 7961
 42.65 7971
 42.70 7981
 42.75 7991
 42.80 8001
 42.85 8011
 42.90 8021
 42.95 8031
 43.00 8041
 43.05 8051
 43.10 8061
 43.15 8071
 43.20 8081
 43.25 8091
 43.30 8101
 43.35 8111
 43.40 8121
 43.45 8131
 43.50 8141
 43.55 8151
 43.60 8161
 43.65 8171
 43.70 8181
 43.75 8191
 43.80 8201
 43.85 8211
 43.90 8221
 43.95 8231
 44.00 8241
 44.05 8251
 44.10 8261
 44.15 8271
 44.20 8281
 44.25 8291
 44.30 8301
 44.35 8311
 44.40 8321
 44.45 8331
 44.50 8341
 44.55 8351
 44.60 8361
 44.65 8371
 44.70 8381
 44.75 8391
 44.80 8401
 44.85 8411
 44.90 8421
 44.95 8431
 45.00 8441
 45.05 8451
 45.10 8461
 45.15 8471
 45.20 8481
 45.25 8491
 45.30 8501
 45.35 8511
 45.40 8521
 45.45 8531
 45.50 8541
 45.55 8551
 45.60 8561
 45.65 8571
 45.70 8581
 45.75 8591
 45.80 8601
 45.85 8611
 45.90 8621
 45.95 8631
 46.00 8641
 46.05 8651
 46.10 8661
 46.15 8671
 46.20 8681
 46.25 8691
 46.30 8701
 46.35 8711
 46.40 8721
 46.45 8731
 46.50 8741
 46.55 8751
 46.60 8761
 46.65 8771
 46.70 8781
 46.75 8791
 46.80 8801
 46.85 8811
 46.90 8821
 46.95 8831
 47.00 8841
 47.05 8851
 47.10 8861
 47.15 8871
 47.20 8881
 47

9.55115.0
 10.00120.0
 10.05121.0
 10.10122.0
 10.15123.0
 10.20124.0
 10.25125.0
 10.30126.0
 10.35127.0
 10.40128.0
 10.45129.0
 10.50130.0
 10.55131.0
 11.00132.0
 11.05133.0
 11.10134.0
 11.15135.0
 11.20136.0
 11.25137.0
 11.30138.0
 11.35139.0
 11.40140.0
 11.45141.0
 11.50142.0
 11.55143.0
 12.00144.0
 12.05145.0
 12.10146.0
 12.15147.0
 12.20148.0
 12.25149.0
 12.30150.0
 12.35151.0
 12.40152.0
 12.45153.0
 12.50154.0
 12.55155.0
 13.00156.0
 13.05157.0
 13.10158.0
 13.15159.0
 13.20160.0
 13.25161.0
 13.30162.0
 13.35163.0
 13.40164.0
 13.45165.0
 13.50166.0
 13.55167.0
 14.00168.0
 14.05169.0
 14.10170.0
 14.15171.0
 14.20172.0
 14.25173.0
 14.30174.0
 14.35175.0
 14.40176.0
 14.45177.0
 14.50178.0
 14.55179.0
 15.00180.0

20.15243.10
 20.20246.10
 20.25249.10
 20.30246.10
 20.35247.10
 20.40248.10
 20.45249.10
 20.50250.10
 20.55251.10
 21.00252.10
 21.05253.10
 21.10254.10
 21.15255.10
 21.20256.10
 21.25257.10
 21.30258.10
 21.35259.10
 21.40260.10
 21.45261.10
 21.50262.10
 21.55263.10
 22.00264.10
 22.05265.10
 22.10266.10
 22.15267.10
 22.20268.10
 22.25269.10
 22.30270.10
 22.35271.10
 22.40272.10
 22.45273.10
 22.50274.10
 22.55275.10
 23.00276.10
 23.05277.10
 23.10278.10
 23.15279.10
 23.20280.10
 23.25281.10
 23.30282.10
 23.35283.10
 23.40284.10
 23.45285.10
 23.50286.10
 23.55287.10
 24.00288.10

PIAK FLOW AND STORAGE (END OF PERIOD). SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

LOCATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS										
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9	RATIO 10	RATIO 11
HYDROGRAPH AT	000001	.15	1	87.	174.	261.	348.	609.	870.	1131.	1392.	1740.		
	(.35)	(2.46)	4.93	7.39	9.85	17.24	24.63	32.02	39.41	49.26		
REDUCED TO	000002	.15	1	11.	21.	39.	303.	565.	812.	1080.	1360.	1733.		
	(.39)	(.32)	.60	3.94	8.58	16.00	22.99	30.57	38.51	49.07		

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1		ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM	
		STORAGE		756.60		756.60		759.70	
		OUTFLOW		0.		0.		14.	
				0.		0.		16.	
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.05	758.67	0.00	8.	11.	0.00	18.08	0.00		
.10	760.16	.46	17.	21.	4.58	18.17	0.00		
.15	760.52	.82	19.	139.	5.58	16.00	0.00		
.20	760.76	1.06	21.	303.	6.75	15.83	0.00		
.35	761.02	1.32	22.	565.	9.42	15.75	0.00		
.50	761.21	1.51	24.	812.	11.58	15.75	0.00		
.65	761.37	1.67	25.	1080.	12.50	15.75	0.00		
.80	761.52	1.82	26.	1360.	13.58	15.75	0.00		
1.00	761.68	1.98	27.	1733.	14.42	15.75	0.00		